

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>Land, level.</p> <p>Soil, 1st rate.</p>
	<p>East on random through N. $\frac{1}{2}$ of Sec. 34.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 33 and 34, set temporary cors. at 20, 40 and 60 chains, and at</p>
80.12	Intersect E. bdy. 72 lks. N. of 1/16 sec. cor. Thence N. 89° 29' West on true line
20.03	Set basalt stone 12x8x6 ins. 8 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face. Dug pits 18x18x12 ins. E. and W. of stone, 5 $\frac{1}{2}$ ft. dist., and raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
20.50	Fence and leave field N. and S.
40.06	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
60.09	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit, drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.12	To point of beginning.
	<p>Land, rolling.</p> <p>Soil, 1st rate. Partly cultivated.</p>
	<p>East on random through S $\frac{1}{2}$ of Sec. 27.</p> <p style="text-align: center;">Va. 21° East</p> <p>Commencing at 1/16 sec. cor. 20 chains N. of SW. cor. of Sec. 27, set temporary cors. at 20, 40 and 60 chains, and at</p>