

## Sub-Subdivisions of T. 3 North, R. 34 East

Chains	
	base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.
60.09	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
80.12	To point of beginning. Land, rolling. Soil, 1st rate.
	East on random through N. $\frac{1}{2}$ of Sec. 15. Va. 21° East.
	Commencing at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 15 and 16, set temporary cors. at 20, 40 and 60 chains, and at
80.20	Intersect E. bdy. 110 lks. N. of 1/16 sec. cor. Thence N.89°13' W. on true line.
20.05	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
40.10	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
60.15	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked