

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	<p>Land, rolling.</p> <p>Soil, 1st rate. <span style="float: right;">Oct. 4, 1887.</span></p>
	<p>East on random through S. <math>\frac{1}{2}</math> of Sec. 16.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Commencing at 1/16 sec. cor. 20 chains N. of SW. cor. of Sec. 16, set temporary cors. at 20, 40 and 60 chains, and at</p>
79.80	<p>Intersect E. bdy. at 1/16 sec. cor. Thence West on true line.</p>
19.95	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
39.90	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit, drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
59.85	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5<math>\frac{1}{2}</math> ft. dist. Raised mound of earth 1<math>\frac{1}{2}</math> ft. high, 3<math>\frac{1}{2}</math> ft. base over it, and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.</p>
79.80	<p>To point of beginning.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p>
	<p>East on random through Center of Sec. 16.</p> <p style="text-align: center;">Va. 21° East.</p> <p>Commencing at <math>\frac{1}{4}</math> sec. cor. bet. Secs. 16 and 17, set temporary cors. at 20, 40 and 60 chains, and at</p>
79.92	<p>Intersect E. bdy. 7 lks. N. of <math>\frac{1}{4}</math> sec. cor. Thence</p>