

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	Setting temporary cor. at 20 chs.
39.70	Intersect E. bdy. 12. lks. N. of $\frac{1}{4}$ sec. cor. Thence N.89°50' W. on true line.
19.85	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. & W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.70	The $\frac{1}{4}$ sec. corner. Land, level. Soil, 1st rate. Not cultivated.
East on random through Center of SE $\frac{1}{4}$ of Sec. 20. Va. 20° East.	
Beginning at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. on S. bdy. of Sec. 20, set temporary cor. at 20 chains, and at	
39.96	Intersect E. bdy. of Sec. 8 lks. N. of 1/16 sec. cor. Thence N. 89°53' W. on true line
19.98	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, 5 $\frac{1}{2}$ ft. dist. Raised mound of earth, 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
39.96	To point of beginning. Land, level. Soil, 1st rate. Not improved.
Oct. 6, 1887.	
West on random through S. $\frac{1}{2}$ of Sec. 31. Va. 20 $\frac{1}{2}$ ° East. Commencing at 1/16 sec. cor. 20 chains S. of $\frac{1}{4}$ sec. cor. bet. Secs. 31 and 32, set temporary cors. at 20, 40 and 60 chains, and at	