

Sub-Subdivisions of T. 3 North, R. 34 East

Chains	long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
34.70	Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth, $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on N. face.
54.70	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground and marked 1/16 S on N. face.
74.70	To point of commencement. Land, level. Soil, 1st rate.  Oct. 12th
West on random through N. $\frac{1}{2}$ of Sec. 31. Va. 20° East.	
Commencing at 1/16 sec. cor. 20 chains N. of $\frac{1}{4}$ sec. cor. bet. Secs. 31 and 32, set temporary cors. at 20, 40 and 60 chains, and at	
74.75	Intersect W. bdy. 110 lks. S. of 1/16 sec. cor. Thence South 89°10' East on true line.
14.75	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove stake, 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 S on N. face.
34.75	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor. Dug pits 18x18x12 ins. E. and W. of stake, $5\frac{1}{2}$ ft. dist. Raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it, and in E. pit drove a stake, 2 ft.