

S.Bdy. of T. 4 N. 4 35 E.  
 As surveyed by W.H.Odell.  
 Under Contract No.110.  
 Dated Feb. 7, 1865.

Chains	
	<p>From the corner of Township 3 &amp; 4. North of Ranges 35 and 36.</p> <p>West on random between Township 3 &amp; 4 North Range 35 E. At 40.00 and 80.00 chs. Set mile and half Mile post, at 483.00. Intersect N. &amp; S. line 1.50 chs.</p> <p>South of post corner for Township 3 and N. Ranges 34 &amp; 35 E., Hence the Correction will be S. 89°49' East on True line.</p> <p style="text-align: right;">----- June 2nd. 1865.</p> <p>S. 89°49' E. on true line on South boundary of Section 31 T. 4, N. R. 35 E.</p> <p style="text-align: right;">Var. 21° East.</p>
43.00	Set $\frac{1}{4}$ section post, on level, drove charred stake, dug pits and raised mound as per instructions.
80.00	<p>Set a post corner for sections 5 &amp; 6, 31 &amp; 32, on level, drove charred stake, dug pits and raised mound as per instructions.</p> <p>Land gently rolling.</p> <p>Grass good.</p> <p>Soil good 2nd rate.</p>
	<p>S. 89°49' East on true line on South boundary of Section 32 Township 4. N. R. 35 East</p> <p style="text-align: right;">Va. 21° East.</p>
40.00	Set $\frac{1}{4}$ Section post, on level drove charred stake dug pits and raised mound as per instructions.
80.00	<p>Set a post corner for 32 &amp; 33, 4 &amp; 5 on level, drove charred stake dug pits and raised mound as per instructions.</p> <p>Land gently rolling.</p> <p>Good grass, Soil good. 2nd rate.</p>
	<p>S. 89°49' East on true line on South boundary of Section 33 Township 4 N. R, 35 East.</p> <p style="text-align: right;">Va. 21° East.</p>