

S. Bdy. of T. 4 N., R. 35 Es.

| | | |
|--------|--|------|
| Chains | | |
| 19.00 | Wild Horse Creek 8 lks. wide, course N.W. | |
| 39.50 | Road course North | ‡30 |
| 40.00 | Set $\frac{1}{4}$ Sec. post, corner, drove charred stake, dug pits and raised mound as per instructions. | |
| 80.00 | Set a post corner for Sections 33 & 34, 3 & 4. Land gently ascend to the N. Drove charred stake, dug pits and raised mound as per instructions. Land gently rolling. Good grass, soil good, 2nd rate. | |
| <hr/> | | |
| | S. 89° 49' East on true line, on South boundary of Sec. 34 T. 4 N. Range 35 East. | |
| | Var. 21° E. | |
| 40.00 | Set $\frac{1}{4}$ Sec. on post corner, drove charred stake, dug pits and raised mound as per instructions. | |
| 80.00 | Set a post corner for. Secs. 34 & 35, 2 & 3. Land slopes to The south west, deposited marked stone, dug pits, and raised mound as per instructions. Land rolling. Soil, 2nd rate. | ‡40 |
| <hr/> | | |
| | South 89°49' East on true line, on South boundary of Secs. 35 T. 4 N. R. 35 E. | |
| | Va. 21°30'E. | |
| 21.00 | Road course N. W. | ‡140 |
| 40.00 | Set $\frac{1}{4}$ Sec. post cor. in edge of ravine course N. Drove charred stake, dug pits, and raised mound as per instructions. | ‡50 |
| 80.00 | Set a post cor. for sections 35 & 36, 1 & 2, on side hill slopes the N., from which A pine, 30 ins. diam., bears N. 74°E. 75 lks. No other tree near, dug pits & raise mound as per instructions. Land broken, soil 2nd rate. | |