

S Bdy. of T. 4 N., R. 35 E.

Under Contract No. 110 bearing date February 7th 1865,
as will appear from affidavits made, at the close of said
contract, in due form and attached to the field notes
of the exterior lines of townships No. 6 N. of Range East.

William H. Odell,
Deputy Surveyor.

Survey of the exterior lines of Township number 3 North
of Range 35 East of Willamette Meridian in the State
of Oregon, by William H. Odell deputy surveyor, under his
contract No. 114 bearing date July 2nd 1886.
Commenced July 26th and completed July 31st. 1886.

North Bdy. of T. 3 N. R. 35 East.

West on Random on north boundary of Township.

Var. 19° East

On north boundaries of Secs 1, 2, 3, 4, 5 & 6 set half
mile and mile post and intersect west boundary in
476.90 chs. 57 lks. north of post corner for Township
3 & 4, North Ranges 34 & 35 east,

Therefore the correction will be North $89^{\circ} 56'$ east. on
true line.

July 30th 1866

36.90 N. $89^{\circ} 56'$ East on true line, north boundary of Sec. 6.
Set post corner for $\frac{1}{4}$ Sec. Drove charred stake dug pits,
and raised mound as per instructions.

76.90 Set post cor. for Secs. 5, 6, 31 and 32. Drove charred stake
and raised mound as per instructions.

Land gently rolling.
Prairie grass, good soil 2nd rate.

40.00 N. $89^{\circ} 56'$ East on North boundary of Sec. 5
Var. 20° E.
Set post corner for $\frac{1}{4}$ Sec., drove charred stake, dug
pits and raised mound as per instructions.