

## Township 3 North Range 35 East.

Chains		
80.00	Set post corner for Sec. 4,5,32& 33, drove charred stake, dug pits and raised mound as per instructions. Land gently rolling, good grass, soil 2nd rate.	
	N. 89° 56' E. on north boundary of Sec. 4 Var. 20° E.	
9.60	Wild Horse Creek 5 lks. wide, course North West , Enter field course	-10
17.10	Leave Field.	
27.10	Road Course North and South	+20
40.00	Set post corner for $\frac{1}{4}$ Sec., drove charred stake, dug pits, and raised mound as per instructions.	+5
51.50	Stage Road from Walla Walla to Boise City course N. & S.	
80.00	Set post corner for Secs. 3,4,33 and 34, drove charred stake, dug pits, and raised mound as per instructions. Land broken, grass good. Soil on west side of Wild Horse Creek and in field 1st rate balance 2nd rate.	
	N. 89° 56' E. on North boundary of Sec. 3 Var. 20° E.	
40.00	Set post corner for $\frac{1}{4}$ sec. drove charred stake dug pits and raised mound as per instructions.	+30
80.00	Set post corner for Sec. 2,3,34&35, drove charred stake, dug pits and raised mound as per instructions. Land broken, good grass. Soil good 2nd rate.	+75
	N. 89° 56' East on North boundary of Sec. 2. Var. 18° East.	
40.00	Set post corner for $\frac{1}{4}$ Sec. on hill side facing the west, drove charred stake, dug pits and raised mound as per instructions.	
80.00	Set post corner for sections. 1,2, 35&36, from which A pine, 12 ins. diam. bears N 15° W. 166 lks. A pine, 28 ins. diam. bears N. 1° E. 90 lks. A pine, 30 ins. diam. bears S. 2° E. 102 lks. No tree near in section 2 Land broken, good grass. Soil good 2nd rate.	-200