

Township 3 North Range 35 East

Chains	N. 89° 56' East on south boundary of Sec. 36 Var. 20° 30' East.	
4.60	Pine Creek 8 lks. wide, course North.	
40.00	Set post corner for $\frac{1}{4}$ Sec. above charred stake dug pits, raised mound as per instructions.	+350
80.00	To post corner, land broken and rocky, grass good. July 31st 1866	-150
<p>The greater part of this township is included in the Umatilla Indian Reservation. The lands are rich and very productive whenever there is sufficient moisture to prevent the long dry summer from parching up the lands</p> <p>On all the land there is a heavy growth of rich bunch grass. Upon considerable portion of land not included in the reservation valuable claims have been located hence that portion should be subdivided</p>		
<p>A list of names of the subdividuals employed to assist in running, measuring, or marking, the lines and corners described in the forgoing fields notes of Township number 3 North of the base line of Range 35 East of Willamette Meridan, showing the respective capacities in which they acted.</p> <p style="text-align: center;">J. J. Henderson Chairman John A Rigg Axeman P. W. Denny</p> <p style="text-align: center;">East Boundary. William H. Odell-Contract 114</p>		
<p>North on East Boundary of Sec. 36 Var. 21° East.</p>		
40.00	Set post corner for $\frac{1}{4}$ Sec. from which A pine 10 ins. diam., bears S. 12° E. 2.50 lks. A pine 10 ins. diam., bears N. 2° W. 1.75 lks	-125
57.15	Boise City Stage Road Course East and West	-50
69.50	Umatilla River 1.00 chs wide course West.	-15
80.00	Set a basalt stone 7x9x15 corner for Sections 25, 36, 30 & 31 on hill side facing the south. Land broken and rocky, grass good Balm and pine timber along margin of the river.	+80