

Township 3 North Range 35 E. W. M.

Chains	<p>North on random between Secs. 1 & 2.</p> <p>40.00 Set temp. $\frac{1}{4}$ Sec. corner.</p> <p>79.35 Intersect North Bdy, 29 lks. West of post corner. S. $0^{\circ} 12'$ W. on true line.</p> <p>39.35 Set post cor. for $\frac{1}{4}$ Sec. drove charred stake, dug pits, raised mound as per instructions.</p> <p>79.35 To post cor. Land hilly, good grass, soil 2nd rate.</p> <hr/> <p>West between Secs. 11 & 14</p> <p>9.00 Wildhorse Creek channel dry course N. W.</p> <p>40.00 Set post. cor. for $\frac{1}{4}$ Sec. drove charred stake, dug pits, and raised mound as per instructions.</p> <p>79.00 Road course S. E. & N.W.</p> <p>80.00 Set post cor for Secs. 10, 11, 14 & 15, drove charred stake, dug pits, and raised mound as per instructions. Land hilly, good grass. soil 1st rate.</p> <hr/> <p>North between Secs. 10 & 11 Var. 21° East.</p> <p>30.00 Begin to descend hill.</p> <p>40.00 Set post cor. for $\frac{1}{4}$ Sec. drove charred stake, dug pits raised mound as per instructions.</p> <p>80.00 Set post cor. for Secs. 2, 3, 10 & 11, in bed of Wildhorse Creek, channel dry course N. 75° W. from which cor. A balm, 6 ins. diam., bears N. 70° E. 60 lks. A pine, 18 ins. diam., bears N. 50° E. 125 lks. A balm, 4 ins. diam., bears S. 30° E. 100 lks. No other tree near mound of stones. Land hilly, good grass, soil 1st rate. August 28, 1866.</p> <hr/> <p>East on random between Secs. 2 & 11. Var. $20^{\circ} 30'$ East.</p>	<p>+100</p> <p>-60</p> <p>+400</p> <p>+150</p> <p>-60</p> <p>-20</p>
--------	---	--