

Township 3 North Range 35 East W. M.

Chains	
40.00	Set temp. $\frac{1}{4}$ Sec. corner.
80.37	Intersect N. & S. line 54 lks. South of post corner. S $89^{\circ} 37'$ W. on true line.
40.18	Set post cor. for $\frac{1}{4}$ Sec., drove charred stake, dug pits, and raised mound as per instructions.
80.37	To post corner, land hilly, good grass, soil 1st. rate.
North on random between Secs. 2 & 3.	
40.00	Set temp. $\frac{1}{4}$ Sec. corner.
80.20	Intersect N. Edy. 10 lks. W. of post cor. S. $80^{\circ} 04'$ W. on true line.
40.20	Set post cor. for $\frac{1}{4}$ Sec. cor., drove charred stake, dug pits, and raised mound as per instructions.
80.20	To post corner. Land rolling, good grass, soil 1st rate.
West between Secs. 3 & 10.	
40.00	Set post cor. for $\frac{1}{4}$ Sec., drove charred stake, dug pits, and raised mound as per instructions. Var. 17° East.
80.00	Set post cor. Secs. 3, 4, 9 & 10, in gulch course N. drove charred stake, dug pits and raised mound as per instructions. This line passes over bottom land on south bank of Wilfhorse Creek. Soil 1st rate.
North on random between Secs. 3 & 4	
Var. 21° East.	
40.00	Set temp. $\frac{1}{4}$ Section corner.
80.12	Intersect North Boundary 20 links. West of post corner, S. $00^{\circ} 09'$ W. on true line
40.12	Set post cor. for $\frac{1}{4}$ Section, drove charred stake, dug pits, and raised mound as per instructios.