

Township 3 North, Range 35 E. W. M.

Chains		
69.25	Wildhorse Creek channel dry course West.	-75
80.12	To post corner, land broken, good grass, soil 1st rate.	
<hr/>		
	W. between Sections 4 & 9	
30.25	Boise City and Walla Walla Stage Road course N. & S.	
33.25	Spring branch course north.	
40.00	Set post corner for $\frac{1}{4}$ Sec. drove charred stake, dug pits, raised mound as per instructions.	
80.00	Set post corner for sections, 4, 5, 8 & 9, drove charred stake, dug pits and raised mound as per instructions. Land rolling, good grass, soil good 2nd rate.	+ 30
<hr/>		
	North on random between Secs. 4 & 5	
	Var. 21° East	
40.00	Set temporary $\frac{1}{4}$ section corner.	
80.19	Intersect northern boundary 62 links	
	West of post corner,	
	S. $00^{\circ} 27'$ W. on true line.	
40.19	Set post corner for $\frac{1}{4}$ section, drove charred stake, dug pits and raised mound as per instructions.	
80.19	To post corner, land rolling, good grass, soil 1st rate. East Boundary as surveyed by Z. F. Moody. Under contract. #164- October 4, 1871.	+ 30
<hr/>		
	North on East boundary of Secs 35	
	Var. $20^{\circ} 30'$ East	
40.00	Set post and made stone mound for $\frac{1}{4}$ Sec. cor.	
56.40	Old Stage Road corner E. & W.	
67.50	Umatilla River 150 lks. flows W.	
80.00	Set stone, 16x14x9 for cor. to sections 30, 31, 35 & 36. Land broken, soil stony, good grass.	
<hr/>		
	North on East Bdy of Sec. 25.	
	Var. 20° E.	
40.00	Set stone 16x14x9 for $\frac{1}{4}$ Sec. cor.	
80.00	Set post and made mound of stone for cor. to Sec. 24, 25, 19 & 30	