

Township 3 North, Range 35 East of the W. M.

Chains		
	North bet Secs. 23 & 24	
40.00	Set post and made mound of earth for $\frac{1}{4}$ S. cor.	
80.00	Set post and made mound of earth for cor. to Secs. 23, 24, 13 & 14	
	Land slightly broken, soil 1st rate, good grass	
	East on random bet. Secs. 13 & 24	
	Var. 20° E.	
40.00	Set temporary $\frac{1}{4}$ S. cor.	
80.00	Intersect E. bdy. 21 lks. S. of cor. S. 80° 51' W. on true line.	
40.00	Set post and made mound of stone for $\frac{1}{4}$ Sec. cor.	
61.50	Bottom of Gulch.	-340
80.00	To corner. Land broken, good grass.	
	North bet. Secs. 13 & 14	
31.00	Dim Wagon Road E. & W.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.	
76.50	To Wildhorse creek. Boundary of reservation. Land broken, some good pine and fir timber.	
	North bet. Secs. 34 & 35.	
40.00	Set post and made earth mound for $\frac{1}{4}$ Sec. cor.	
63.00	Umatilla River 200 lks. flows W.	
80.00	Set post and made mound of earth for cor. to Secs. 34, 35, 26 & 27. Land rolling, soil 2nd rate, good grass.	
	East on random bet. secs. 26 and 35	
	V. 21° E.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor.	
79.76	Intersect N. & S. line 18 N. of cor. N. 89° 52' W. on true line	
39.00	Dry bed of gulch, course S. W.	
39.88	Set stone 18x10x9 for $\frac{1}{4}$ S. cor.	-175