

Township 3 North 35 East of the W. M.

Chains 79.76	To cor. Land broken, soil 2nd rate, good grass
	North bet. Secs. 26 & 27
40.00	Set stone 18x14x8 for $\frac{1}{4}$ S. cor.
80.00	Set post and made mound for cor. to Secs. 26, 27, 22 & 23. Land level, soil 1st rate
	East on random bet. 23 & 26 V. 20° 30' E.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.10	Intersected N. & S. line 17 lks. N. of cor. N. 89° 52' W, on true line.
40.05	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.
80.10	To cor. Land level, soil good.
	N. bet. Secs. 22 & 23
40.00	Set stone 18x14x10 for $\frac{1}{4}$ Sec. cor.
80.00	Set post and made mound of earth for cor. to Secs. 22, 23, 14, 15. Land generally level, soil 1st rate, good grass.
	East on random bet. Secs. 14 & 23 V. 21° E.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
79.86	Intersected N. & S. line at cor., W. on true line.
39.93	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.
79.86	To cor. Land level, soil good, first rate grass.
	North bet. Secs. 14 & 15
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.
80.00	Set post for cor. to Secs. 10, 11, 14 & 15. Land level, soil good, good grass.