

## Township 3 North Range 35 East of the W. M.

Chains 80.00	To corner.  Land generally level, soil 1st rate, good grass.
40.00 80.00	North bet. Secs. 9 & 10. Set post and made earth mound for $\frac{1}{4}$ sec. corner. Set post and made mound of earth for cor. to Secs. 9, 10, 3 & 4. Land level, soil first rate, good grass.
40.00 80.14 40.07 80.14	East on random bet. Secs. 3 & 10 V. $21^{\circ}$ E. Set temporary $\frac{1}{4}$ S. cor. Intersected N. & S. line at corner West on true line. Set post and made mound of earth for $\frac{1}{4}$ Sec. cor. To corner. Land level, soil 1st rate, good grass.
14.00	North bet. Secs. 3 & 4. Intersected Wild Horse ck. Northern Boundary of Reservation. Land rolling, soil 1st rate, good grass. Oct. 20, 1871.
40.00 80.00	North bet. Secs. 32 & 33. Set stone 18x14x9 for $\frac{1}{4}$ S. cor. Set stone 20x12x10 for cor to Secs. 32, 33, 28 & 29 Land rolling, soil good 2nd rate, good grass.
40.00 80.14 40.07	East on random bet. Secs. 28 & 33 W. $21^{\circ}$ 30' E. Set temporary $\frac{1}{4}$ S. cor. Int. N. & S. line 14 lks. N. of cor. N. $89^{\circ}$ 54' W. on true line. Set post and made earth mound for $\frac{1}{4}$ Sec. cor.