

Exteriors of Township 4 North 35 East.

Chains 77.20	To cor. to tps. 3 & 4 N. R. 34 East. Land level; soil 1st rate. good grass.
	<p style="text-align: center;">General Description</p> <p>The land in this Township is generally rolling, soil 2nd rate, good grass.</p>
	<p>Exterior Lines of Township 3 North Range 35 East Willamette Meridan, Oregon, as surveyed by Jas. P. Currin & Jas. E. Noland, U.S. Deputy Surveyor under their special contract dated May 4, 1887.</p>
	<p>Commencing Aug. 24, 1887, on the line bet. Tps. 3 N. R. 35 & 36 E. at cor. to Secs. 7, 12, 13, & 18, which I reestablished from bearing trees: Setting a basalt stone 14x12x10 ins. 9 ins. in the ground, marked 2 notches on N. & 4 notches on S. edges. from which.</p> <p>A pine 24 ins. in diam. bears N. 40° E. dist. 42 lks. marked T 3 N. R 36 E., S 7 B T.</p> <p>A pine 24 ins. in diam. bears S. 40° lks. marked S. 18 B T.</p> <p>A pine 20 ins. in diam. bears S: 55° W. dist. 28 lks. marked T 3 R. 35 E., S 13 B T.</p> <p>A pine 20 ins. in diam. bears North 70° W. dist. 68 lks. marked S 12 B #.</p>
	<p>And having tested my compass by taking an observation on Polaris in accordance with instructions contained in the manuel of surveys and found my compass to be correct I ran, thence S on true line bet. 13 & 18.</p>
	<p style="text-align: right;">Var. 21° E.</p>
177.50	<p>Intersected UPR. bdy. Set basalt stone 14x10x10 ins. 10 in the ground for a meander cor. to Secs. 13 & 18, marked M.C. on S. face. Raised mound of stone over it Pitts impracticable.</p>