

Exteriors of Township 3 North 35 East

Chains		
	4½ ft. base along side. Land rolling, Soil 1st rate, good bunch grass.	
South Bet. Secs. 25 & 30. Var. 24° E.		
	Descend.	
21.80	Canyon Course S. E.	- 350
38.80	Summit course S. E.	+ 200
40.00	Set a basalt stone 9x8x7 6 ins. in the ground for ¼ Sec. cor. marked ¼ on W. face, dug pits 18x18x12 ins. N. and S. of cor. 5½ ft. dist. & raised a mound of earth 1½ ft. high 3½ ft. base alongside.	
52.80	/Canyon Course S. E.	-150
80.00	Set a basalt stone 10x9x8 ins. 6 ins. in the ground for cor. to Secs. 25, 30, 31 & 36, marked 5 notches on N. & 1 notch on S. edges, raised a stone mound over it. Pits practicable. Land mountainous, soil 3rd rate. Good bunch grass. 80.00 chs.	-600
South bet. Secs. 31 & 36. Var 21° E.		
5.60	Umatilla River 125 lks. wide course W	-100
12.10	O.R.&N.R.R. course E. & W.	
19.30	Wagon Road course E. & W.	
40.00	Set a post 36x3x3 ins. 12 ins. in the ground for ¼ Sec. cor. marked ¼ S. on W. face, dug pits 18x18x12 ins. N. & S. of cor. 5½ ft. dist. & raised a mound of earth 1½ ft. high 3½ ft. base around post. Leave River bottom.	
55.80	Summit of ridge course N. W.	+250
66.05	Canyon Course W.	-50
80.00	Set a basalt stone 12x7x5 ins. 8 ins. in the ground for cor. to Tps. 3 N R. 35 & 36 E. No trace of the old corner to Tps. 35 & 36 E., could be found although diligent search was made for the same.	