

Subdivisions of Township 3 North Range 35 East.

Chains		
	And raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over corner.	
56.75	Canon Course S.	-400
83.25	To cor. to Secs. 13, 14, 23 & 24.	
	Land mountainous. 43.25 chs.	
	Good bunch grass.	
	Soil 2nd rate.	
<hr/>		
	South on true line bet. Secs. 23 & 24.	
	Var. 20° East.	
20.00	Set a stone $18 \times 18 \times 12$ ins. 12 ins. in the ground for $1/16$ Sec. cor., marked $1/16$ on W. face. And raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base alongside.	
36.00	Canon Course East.	
40.00	Set a stone $12 \times 10 \times 8$ 8 ins. in the ground for $\frac{1}{4}$ Sec. cor. marked $\frac{1}{4}$ on W. face. And raised a mound of stone over it. Pits impracticable.	
60.00	Set a stone $12 \times 10 \times 8$ ins. 8 ins. in the ground for $1/16$ Sec. cor. marked $1/16$ on W. face, and raised a mound of stone alongside. Pits impracticable.	
63.75	Gulch Course East	-70
80.00	Set a stone $9 \times 8 \times 7$ ins. 6 ins. in the ground for cor. to Secs. 23; 24, 25 & 26. Marked with 2 notches on S. and 1 on East edges. Dug pits $18 \times 18 \times 12$ ins. in each Sec. $5\frac{1}{2}$ ft. dist. And raised a mound of earth 2 ft. high with $4\frac{1}{2}$ ft. base over stone.	
	Land level on first $\frac{1}{2}$ mile.	
	Mountainous on last $\frac{1}{2}$ mile. 40.00 chs.	
	Soil 1st and 4th class Good grass.	
<hr/>		
	East on random bet. Secs. 24 & 25.	
	Var. 23° East.	
40.00	Set temp. $\frac{1}{4}$ Sec. cor.	
83.60	Intersect Township line at cor. to Secs. 24, 25, 19 & 30. Thence West on true line.	