

Subdivisions of Township 3 North Range 35 East.

Chains		
41.75	Set a stone 18x12x8 ins. 12 ins. in the ground for $\frac{1}{4}$ Sec. cor. Marked $\frac{1}{4}$ on N. face and raised a mound of stone around corner. Pits impracticable.	
42.75	Canon Course S.	-80
47.50	Summit of ridge course S.	+100
76.60	Summit of ridge course S.	+100
83.50	To cor. to Secs. 25, 26, 25 & 36 Land mountainous Good bunch grass. Soil 4th class.	83.50 chs.
<hr/>		
	South on random bet. Secs. 35 & 36. Va. $20^{\circ} 45'$ East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor.	
79.72	Intersect Township line 4.09 chs. West of cor. to Secs. 35 & 36. Thence N. $29^{\circ} 55'$ W. on true line.	
14.50	Summit of ridge course N. E.	+200
39.83	Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for $\frac{1}{4}$ Sec. cor. Marked $\frac{1}{4}$ S. on W. face, from which A pine 6 ins. diam. bears N. $88^{\circ}$ E. 36 lks. dist. marked $\frac{1}{4}$ S. B T. A pine, 6 ins. diam. bears S. $35^{\circ}$ W. 31 lks. dist. marked $\frac{1}{4}$ S. B T.	
49.40	Wagon Road at edge of river bottom	-300
51.56	Railroad track bears E. & W.	
67.80	Umatilla River 50 lks. Course W.	
70.00	Leave River Bottom.	
79.83	To cor. to Secs. 25, 26, 35 & 36 Land mountainous. 25, 26, Balm timber in river bottom Good bunch grass Soil 2nd rate.	79.83 chs. +300