

Subdivisions of Township 3 North 35 East.

Chains.	<p>Begining at the cor. to Secs. 2, 3, 10 & 11 which is a stone, in mound of stone marked M.C.U.R. with 5 notches on S. and 2 E. faces, from which</p> <p style="padding-left: 40px;">A pine 18 ins. diam. bears N. 50° East 1.25 chs. dist. marked T 3 N, S 2 B T.</p> <p>Thence South on true line bet. Secs. 10 & 11. East.</p> <p style="text-align: right;">Va. 20° East.</p>	
7.15	<p>Wagon Road Course E. and W.</p> <p>Ascend</p>	
20.00	<p>Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/16 Sec. cor. marked 1/16 S. on W. face. Dug pits 18x18x12 ins. N. & S. from stone 5 1/2 ft. dist. And raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base around post.</p>	
40.00	<p>Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/4 Sec. cor. marked 1/4 S. on W. face. And raised a mound of stone 1 1/2 ft. high with 3 1/2 ft. base around post.</p>	
54.00	<p>Indian Trail course N. E. & S. W.</p>	+100
60.00	<p>Set a post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/4 Sec. cor. marked 1/4 S. on W. face. Dug pits 18x18x12 ins. N. & S from stone 5 1/2 ft. dist. And raised a mound of earth 1 1/2 ft. high with 3 1/2 ft. base over it.</p>	
65.00	<p>Draw on ravine</p>	-15
78.40	<p>Wagon Road Course E. & W.</p>	
80.00	<p>Set a post 4 ft. long 4 ins. sq. 24 ins. in the ground for Cor. to Secs. 10, 11, 14 & 15, marked T 3 N.S. 11 on N.E. R 35 E., S 14 on S.E., S 15 on S.W. & S 10 on N.W. faces. Dug pits 18x18x12 ins. in each Sec. 5 1/2 ft. dist. And raised a mound of earth 2 ft. high with 4 1/2 ft. base around post.</p> <p>Land mountainous. 40.00 chs. Hilly 40.00 chs.</p> <p>Good bunch grass.</p> <p>Soil 1st rate.</p>	+400
	<p>E. on random Between Secs. 11 & 14.</p>	