

Subdivisions of Township 3 North Range 35 East

| Chains | |
|--------|---|
| | dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face. |
| 44.00 | Gulch Course N. |
| 58.08 | Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. and W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face. |
| 77.45 | To Cor. to Secs. 15, 16, 21 & 22. Land rolling and uncultivated. Soil 1st rate. Good bunch grass |
| | S. on true line bet. Sec 21 & 22. Va. 21° East. |
| 5.50 | Road Course E. and W. |
| 7.25 | Road Course E. & W. |
| 20.00 | Set a stone 12x8x6 ins. 8 ins. in the ground for 1/16 S. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. & S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Top of Ridge bears W. |
| 40.00 | Set a stone 12x8x6 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. Cor. marked $\frac{1}{4}$ N. on W. face. Dug pits 18x18x12 ins. N. & S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. |
| 60.00 | Set a stone 12x8x8 ins. 8 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. & S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. |
| 70.00 | Canon Course W. |

100

150