

Subdivisions of Township 3 North Range 35 East

| | |
|-----------------|--|
| Chains 80.00 | <p>Deposited charred stake 12 ins. in the ground for Cor. to Secs. 21, 22, 27 & 28. Dug pits 18x18x12 ins. in each Sec. 5$\frac{1}{2}$ ft. dist. And raised a mound of earth 2 ft. high with 4$\frac{1}{2}$ ft. base over it. In S. E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked T 3 N., S. 22 on N E., R 35 E., S 27 on S E., S 28 on S. W. and S. 21 on N. W. faces with 2 notches on S. and 3 notches on E. edges.</p> <p>Land rolling, some rocks, good grass.</p> <p>Soil 1st rate.</p> |
| 76.90 | <p>East on random bet. S. Secs. 22 & 27.</p> <p>Set temp. cor. at 20, 40, and 60 chs. And at</p> <p>Intersect E. bdy. 35 lks. N. of Cor. to Secs. 22, 23, 26 & 27. Thence</p> <p>N. 89° 45' W. on true line.</p> |
| 19.23 | <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5$\frac{1}{2}$ ft. dist. and raised a mound of earth 1$\frac{1}{2}$ ft. high with 3$\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>Descend gradual slope.</p> |
| 38.45 | <p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. dug pits 18x18x12 ins. E. & W. from stake 5$\frac{1}{2}$ ft. dist. and raised a mound of earth 1$\frac{1}{2}$ ft. high with 3$\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.</p> |
| 57.68 | <p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 in E. & W. from stake 5$\frac{1}{2}$ ft. dist. and raised a mound of earth 1$\frac{1}{2}$ ft. high with 3$\frac{1}{2}$ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p> |
| 76.90 | <p>To Cor. to Secs. 21, 22, 26 & 27.</p> <p>Land mostly uncultivated.</p> <p>Slightly rolling, good grass.</p> <p>Soil 1st rate.</p> |