

## Subdivisions of Township 3 North Range 35 East.

Chains	
	South on true line bet. Sec. 27 & 28. Va. 21° 15' East
10.00	Top of Ridge Course W.
20.00	Set a stone 14x6x6 ins. 9 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. and S. from stone 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it.
23.25	Gulch Course W.
40.00	Set a stone 12x7x5 ins. 8 ins. in the ground for ¼ Sec. Cor. marked ¼ on W. face. Dug pits 18x18x12 ins. N. & S. from stone 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it.
52.00	Wagon Road bears W.
60.00	Set a stone 12x8x4 ins. 8 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N. and S. from stone 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it.
80.00	Deposited charred stake 12 ins. in the ground for cor. to Secs. 27, 28, 33 and 34. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. and raised a mound of earth 2 ft. high with 4½ ft. base over it. In S. E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked T 3 n R. S. 27 on N. E., R 35 E., S 34 on S. E., S 33 on S. W. and S 28 on N. W. faces with 1 notch on S. and 3 notches on E. edges. Land rolling, soil 1st rate, good grass.
	East on random bet. Secs. 27 & 34. Va. 22° East.
	Set temp. Cors. at 20., 40, 60 chs. And at
77.40	Intersect East bdy. at Cor. to Secs. 26, 27, 34 and 35. Thence West on true line.
19.35	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it.