

Subdivisions of Township 3 North Range 35 East.

Chains 40.00	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. and dug pits 18x18x12 ins. N. & S. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In N. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked $\frac{1}{4}$ S. on W. face.</p>
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on W. face.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for Cor. to Secs. 8, 9, 16 & 17. Dug pits 18x18x12 ins. in each Sec. $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In S. E. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked T 3 N, S. 9 on N. E., R 35 E., S 16 on S. E., S 17 on S W. and S. 8 on N. W. faces with 4 notches on E. and S. edges. Land rolling. Well adapted to agriculture. All under cultivation.. Soil 1st rate.</p>
	<p>East on random bet. Sec. 9 & 16 Va. 21° East. Set temp Cors. at 20, 40, and 60 chs. And at.</p>
80.00	<p>Intersect E. bdy at cor. to Secs. 9, 10, 15 & 16. Thence West on true line.</p>
2.00	<p>Ditch and Canon Ascend</p>
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. of stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In East pit drove a stake 2 ft. long and 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.</p>
33.00	<p>Enter field Course N. & S.</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake $5\frac{1}{2}$ ft.</p>