

Subdivisions of Township 3 North Range 35 East.

Chains.	
	<p>From Corner to Secs. 5, 6, 31 & 32. on N. bdy. of Township I run</p> <p>South on true line bet. 5 & 6</p> <p style="text-align: right;">Va 21° East.</p>
1.00	Wagon Road Course E. & W.
20.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face</p>
40.00	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long & 2 ins. sq. 12 ins. in the ground marked ¼ S. on W. face.</p>
47.00	Fence and enter field Course N. E.
60.00	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on W. face.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for Cor. to Secs. 5, 6, 7 & 8. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. and raised a mound of earth 2 ft. high with 4½ ft. base over it. In S.E. pit drove a stake 2ft. long & 2ins. square 12 ins. in the ground marked T 3 N S 5 on N E., R 35 E., S 8 on S.E., S 7 on S. W. and S 6 on N W. faces, with 3 notches on E. and S. edges.</p> <p>Land slightly rolling.</p> <p>All adapted to agricultural purpose, mostly under cultivation</p> <p>Soil good, 1st rate.</p>