

Subdivisions of Township 3 North Range 35 East.

Chains	<p>East on random bet. Secs. 5 & 8 Va. 20° East.</p>
80.24	<p>Set temp. Cor. At 20, 40, and 60.00 chs. And at Intersect N. & S. line 12 lks. S. of cor. to Secs. 4, 5, 8 & 9. Thence S. 89° 55' W. on true line.</p>
19.60	<p>Wagon Road in lane.</p>
20.06	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. and W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face</p>
40.12	<p>Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long & 2 ins. square, 12 ins. in the ground marked ¼ S. on N. face.</p>
60.18	<p>Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. In E. pit drove stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.</p>
80.24	<p>To cor. to Secs. 5, 6, 7 & 8. Land mostly level. Fine agriculture and grain land. Soil 1st rate.</p>
77.38	<p>West on random bet. Secs. 6, & 7 Va. 20° East. Set temp. cors. At 20, 40 and 60 chs. and at Intersect Township line 21 lks. N. of cor. Secs. 6, 7, 1 and 12. Thence N. 89° 51' E. on true line.</p>
75	<p>Fence and center field Course N. & S.</p>