

## Subdivisions of Township 3 North Range 35 East.

Chains	
49.50 60.03	<p>In E pit drove a stake 2 ft. long &amp; 2 ins. square 12 ins. in the ground marked <math>\frac{1}{4}</math> S. on W. face. Wagon Road in lane Course N. W. Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> Sec. Cor. Dug pits 18x18x12 ins. E &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it. In E. pit drove a stake 2 ft. long &amp; 2 ins. square, 12 ins. in the ground marked <math>\frac{1}{16}</math> S. on N. face.</p>
80.04	<p>To Cor. to Secs. 7, 8, 17 &amp; 18. Land rolling, mostly cultivated. Soil 1st rate.</p>
77.43	<p>West on random bet. Secs. 7 &amp; 18 Va. <math>20^{\circ} 15'</math> East. Set temp. cors. at 20, 40 and 60 lks. and at Intersect Township line 16 lks. North of cor. to Secs. 12, 13, 7 and 18.</p>
1.00	<p>Thence N. <math>89^{\circ} 53'</math> E. on true line.</p>
17.43	<p>Road in lane Course N. and S. Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> Sec. Cor. Dug pits 18x18x12 ins. E. &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it. In E. pit drove a stake 2 ft. long &amp; 2 ins. square 12 ins. in the ground marked <math>\frac{1}{16}</math> S. on N. face.</p>
33.40	<p>Fence Course N. W.</p>
37.43	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{4}</math> Sec. Cor. Dug pits 18x18x12 ins. E. &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math> ft. base over it. In E. pit drove a stake 2 ft. long &amp; 2 ins. square, 12 ins. in the ground marked <math>\frac{1}{4}</math> S. on N. face.</p>
50.30	<p>Spring branch 2 lks. wide course N. W.</p>
57.43	<p>Deposited charred stake 12 ins. in the ground for <math>\frac{1}{16}</math> Sec. Cor. Dug pits 18x18x12 ins. E. &amp; W. from stake <math>5\frac{1}{2}</math> ft. dist. and raised a mound of earth <math>1\frac{1}{2}</math> ft. high with <math>3\frac{1}{2}</math></p>