

Subdivisions of Township 3 North Range 35 East.

Chains	Land level and cultivated Soil 1st rate.
	East on random bet. Secs. 17 & 20. Va. 19° 45' East. Set temp Cors. 20, 40 & 60 chs. and at:
80.00	Intersect N. & S. line 12 lks. N. of Cor. to Secs. 16, 17, 20 and 21. Thence N. 89° 55' W. on true line
2.50	Gulch N. W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long and 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked ¼ S. on N. face.
45.00	Dry Ditch
59.85	Fence and leave field course N. and S.
60.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. and W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
80.00	To Cor. to Secs. 17, 18, 19 and 20. Land level and cultivated. Soil 1st rate.
	West on random bet. Secs. 18 & 19. Va. 19° 45' East.
	Set temp. Cors. at 20, 40 and 60 chs. and at
77.17	Intersect Township line 14 lks. N. of Cor. to Secs. 18 19, 13 & 24.