

Subdivisions of Township 3 North Range 35 East.

Chains.	Thence N. 89° 54' E. on true line.
1.25	Wagon Road in lane course N. & S.
16.00	Fence and enter field course N. and S
17.17	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face.
37.17	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x18 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked ¼ S. on N. face.
44.50	Fence and leave field.
57.17	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. & W. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In E. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on N. face
77.17	To Cor. to Secs. 17, 18, 19 & 20. Land level and mostly cultivated. Soil 1st rate.
	South on true line bet. Secs. 19 & 20. Va. 19° 45' East.
.75	Fence and enter field course E. & W.
20.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. N. and S. from stake 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it. In N. pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S. on W. face.
40.00	Deposited charred stake 12 ins. in the ground for ¼ Sec. Cor. Dug pits 18x18x12 ins. N. & S. from stake 5½ ft.