

Subdivisions of Township 3 North Range 35 East.

Chains.	
77.24	<p>In E. pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.</p> <p>To cor. to Secs. 19, 20, 29 & 30.</p> <p>Land rolling uncultivated.</p> <p>Soil 1st rate.</p> <p>Good grass.</p>
13.75	<p>South on true line bet. Secs. 29 & 30.</p> <p style="text-align: right;">Va 21° East.</p> <p>Lane and wagon Road Course E. and W.</p>
20.00	<p>Set a post 3 ft. long 3 ins. square, 24 ins. in the ground for 1/16 Sec. Cor. marked 1/16 S. on W. face.</p> <p>Dug pits 18x18x12 ins. N. and S. from post 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base around post.</p>
40.00	<p>Set a post 3 ft. long 3 ins. square, 24 ins. in the ground for ¼ Sec. Cor. marked ¼ S. on W. face. Dug pits 18x18x12 ins. N. & S. from post 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base over it.</p>
46.00	<p>Spring Branch Course N. W.</p>
58.60	<p>Fence and leave field course E. & W.</p>
60.00	<p>Set a post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 Sec. Cor marked 1/16 S. on W. face. Dug pits 18x18x12 ins. N. & S. from post 5½ ft. dist. and raised a mound of earth 1½ ft. high with 3½ ft. base around post.</p>
80.00	<p>Deposited charred stake 12 ins. in the ground for cor. to Secs. 29, 30, 31 & 32. Dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. and raised a mound of earth 2 ft. high with 4½ ft. base over it. In S. E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked T 3 N. S 29 on N. E., R 35 E., S 32 on S. E., S 31 on S. W. and S 30 on NW W. faces with 5 notches on E. and 1 notch on S. edges.</p> <p>Land rolling and level.</p> <p>Soil 1st rate, Good grass.</p>