

Subdivisions of Township 3 North Range 35 East.

Chains	
	East on random bet. Secs. 29 & 32. Va. 21° East.
	Set temp. Cors. at 20, 40 and 60 chs. And at
80.12	Intersect N. & S. line 15 lks. S. of cor. to Secs. 28,
	29, 32 and 33. Thence 89° 54' W.
	On true line.
20.03	Deposited charred stake 12 ins. in the ground for 1/16
	Sec. Cor. Dug pits 18x18x12 ins. E and W. from stake
	5½ ft. dist. and raised a mound of earth 1½ ft. high
	with 3½ ft. base over it. In East pit drove a stake 2
	ft. long 2 ins. sq. 12 ins. in the ground marked 1/16
	S. on N. face.
40.06	Set a post 3 ft. long 3 ins. square, 24 ins. in the ground
	for ¼ Sec. Cor. marked ¼ S. on N. face Dug pits 18x18x12
	ins. E. & W. from post 5½ ft. dist. and raised a mound
	of earth 1½ ft. high with 3½ ft. base around post.
43.00	Wagon Road Course N. E.
60.08	Set a post 3 ft. long 3 ins. square 24 ins. in the ground
	for 1/16 S. on N. face. Dug pits 18x18x12 ins. E. and
	W. from post 5½ ft. dist. and raised a mound of earth
	1½ ft. high with 3½ ft. base around it.
80.12	To Cor. to Secs. 29, 30, 31 & 32.
	Land rolling, uncultivated. Soil 1st rate.
	Good grass.
	<hr/>
	West on random Bet. Secs. 30 & 31
	Va. 21° East.
	Set temp. Cors. at 20, 40 and 60 chs. and at
77.00	Intersect Township line 33 lks. N. of Cors. to Secs. 30,
	31, 25 and 36. Thence
	N. 89° 46' East on true line.
17.00	Deposited charred stake 12 ins. in the ground for 1/16
	Sec. Cor. Dug pits 18x18x12 ins. E. and W. from stake
	5½ ft. dist. and raised a mound of earth 1½ ft. high
	with 3½ ft. base over it.