

## Subdivisions of Township 3 North Range 35 East

Chains	
19.47	In East pit <sup>drove</sup> a stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
37.00	Fence and leave field course N. Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ Sec. Cor. Dug pits 18x18x12 ins. E. and W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. square 12 ins. in the ground marked $\frac{1}{4}$ S. on N. face.
57.00	Deposited charred stake 12 ins. in the ground for 1/16 Sec. Cor. Dug pits 18x18x12 ins. E. and W. from stake $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. In East pit drove a stake 2 ft. long 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face.
75.25	Wagon Road Course N. E.
77.00	To Cors. to Secs. 29, 30, 31 and 32. Land level and uncultivated. Soil 1st rate. - Good grass.
	South on random bet. Secs. 31 and 32. Va. 21° East.
79.50	Set temp. Cors. at 20, 40 and 60 chs. and at Intersect Township line 2.10 chs. West of Cors. to Secs. 30 and 31. Thence N 1° 30' W. on true line
7.00	Umatilla River 1.10 chs. wide and Leave bottom.
19.50	Set stone 12x10x8 ins. 8 ins. in the ground for 1/16 Sec. Cor. marked 1/16 on W. face. Dug pits 18x18x12 ins. N & S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it.
39.50	Set a stone 12x10x6 ins. 8 ins. in the ground for Sec. Cor. marked $\frac{1}{4}$ on W. face. Dug pits 18x18x12 ins. N. and S. from stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it.