

Allotment

Section 11

Subdivision of Township 3 North Range 35 East

Chains 10.00	Set a basalt stone 12x9x5 ins. 8 ins. in the ground for 1/16 & 1/32 Sec. corner marked 1/16 on S. & 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ ft. base over it.	
20.00	Set a basalt stone 9x8x7 ins. 7 ins. in the ground for 1/16 & 1/32 Sec. corner, marked 1/16 on S. and 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. & raised a mound of earth 1½ ft. high 3½ ft. base over it.	
25.00	Descend to	-100
30.00	Set a post 3 ft. long 3 ins. sq. with marked stone 12 ins. in the ground for 1/32 Sec. cor. marked 1/32 S. on W. face, on steep East slope, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. raised a mound of earth 1½ ft. high 3½ ft. base over it. Land mostly level. Soil 1st rate. & rich. Good grass.	
16.00	Descend through brush.	
20.00	Set basalt stone 9x8x7 ins. 6 ins. in the ground for 1/32 S. corner marked 1/32 on W. face; from which A pine 8 ins. diam. brs. N. 85° W. 9 lks. dist. marked 1/32 S B T. A pine 14 ins. diam. brs E. 27 lks. dist marked 1/32 S B T. Land level. Soil 1st rate. Good grass.	-20

Var. 20° East.

Var. 20° East.