

Allotment  
Section 11  
Subdivision of Township 3 North Range 35 East.

Chains	
	<p>From the 1/32 Sec corner 10 chains E. of the 1/4 Sec. cor. between Secs. 10 &amp; 11. I run West on random line in Sec. 11. Var. 19° 00' E.</p>
10.00	<p>Intersect the N. &amp; S. line 4 lks. S. of 1/4 Sec. corner bet. Secs. 10 &amp; 11. Post gone replaced it with a stone 12x9x7 ins. set 8 ins. in the ground marked 1/4 on W. face, and raised the old mound of stone over it. Thence I run S. 89° 46' E. on true line in Sec. 11. Var. 19° E.</p>
10.00	<p>To 1/32 Sec. corner 10 chains E. of 1/4 Sec. corner between Secs. 10 &amp; 11.  Land level, except N. W. Corner steep. Soil 1st rate &amp; brushy. Good Grass.</p>
Section 13	
	<p>From the 1/4 Sec. corner between Secs. 13 and 14 which is a stone 12x8x6 ins. 8 ins. in the ground marked 1/4 on W. face, with pits 18x18x12 ins. N. &amp; S. of stone 5 1/2 ft. dist. &amp; mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. I run East on random line through the center of Sec. 13 Var. 20° E.</p>
	<p>Setting temporary corners at every 20, 40 &amp; 60 chains and at</p>
83.40	<p>Intersect the N. &amp; S line at 1/4 Sec. corner between Secs. 13 and 18 which is a basalt stone 9x8x7 ins. 6 ins. in the ground marked 1/4 on W. face from which</p>