

Allotment

Section 13

Subdivision of

Chains		
	<p>A pine 24 ins. diam brs. N. 50° E. 22lks. dist. marked $\frac{1}{4}$ S. B. T.</p> <p>A pine 16 ins. diam. brs S. 83° W. 30 lks. dist. marked $\frac{1}{4}$ S.B.T. Thence I run</p> <p>West on true line through the center of Section 13 Var. 20° E.</p> <p>Descend</p>	
20.40	Gulch course North.	
20.85	<p>Set post 3 ft. long 3 ins. square 24 ins. in the ground for 1/16 Sec. corner marked 1/16 S. on N. face, dug pits 18x18x12 ins. E. & W. of post $5\frac{1}{2}$ dist. and raised a mound of earth $1\frac{1}{2}$ ft. high & $3\frac{1}{2}$ ft. base around it.</p>	
41.70	<p>Set a basalt stone 12x8x6 ins. 8 ins. in the ground for $\frac{1}{4}$ Sec. corner marked $\frac{1}{4}$ on N. face; dug pits 18x18x12 ins. E. & W of stone $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.</p> <p>Descend through Pine Timber.</p>	
49.30	<p>Canyon course North.</p> <p>Ascend.</p>	-250
62.55	<p>Set post 3 ft. long 3 ins. square with marked stone 12 ins. in the ground for 1/16 Sec. corner marked 1/16 S. on N. face, dug pits 18x18x12 ins. E. & W. of post, $5\frac{1}{2}$ ft. dist and raised a mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base around post.</p>	
65.40	Summit begin descend to	+250
71.40	Level plateau	
83.40	<p>The $\frac{1}{4}$ Sec. corner between Secs. 13 & 14.</p> <p>Land mountainous & rolling</p> <p>Soil 1st & 2nd rate.</p> <p>Grass.</p>	