

79  
Allotment

Section 13

Subdivision of Township 3 North Range 35 East.

Chains

From the 1/16 Sec. corner 20 chains N. of corner to Secs 13, 14, 23 & 24 which is a stone 10x8x7 ins. 7 ins. in the ground marked 1/16 on W. face, pits 18x18x12 ins. N. & S. of stone 5½ ft. dist & mound of earth 1½ ft. high 3½ ft. base over it.

I run

East on random line through the S. ½ of Sec. 13.

Var. 21° E.

Setting temporary corner at 20, 40 and 60 chains at

83.70 Intersect the East bdy. of Township 10 lks. S. of 1/16 Sec. corner between Sec. 13 & 18 which is a stone 9x8x7 ins. 6 ins. in the ground marked 1/16 on W. face, with pits 18x18x12 ins. N. & S. of stone 5½ ft. dist. & mound of earth 1½ ft. high 3½ ft. base over it.

Thence I run

S. 89° 56' W. on true line through the S ½ of Sec. 13.

Var. 21° E.

7.70 Gulch course S. W.

16.70 Foot of hill

20.92 Set a stone 12x11x5 ins. 8 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face, raised mound of stone over it.

Pits impracticable

35.20 Summit

41.85 Set stone 14x8x5 ins. 10 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face, and raised a mound of stone over it.