

Subdivision of Township 3 North Range 35 East.

Chains 19.81	Set stone 9x8x7 ins. 6 ins. in the ground for 1/16 Sec. cor. marked 1/16 on N. face dug pits 18x18x12 ins. E & W. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.
41.62	To corner to Secs. 13-18-19 and 24. Land rolling Timber East part. Good Grass.
	From the 1/16 Sec. corner 20 chs. S. of the cor. to Secs. 13-18-19 & 24 which is a post 3 ins. sq. firmly set in the ground marked 1/16 S on W face with pits 18x18x12 ins. N. & S. of post 5½ ft. dist. and mound of earth 1½ ft. high 3½ ft. base around post. I run West on true line in Section 24. Var. 19° E.
20.80	Over rolling ground Set a stone 10x8x6 ins. 6 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face and raised a mound of stone over it. Pits impracticable.
35.00	Descend.
41.60	Set stone 9x8x7 ins. 6 ins. in the ground for 1/16 & 1/32 Sec. corner marked 1/16 on N. and 1/32 on S. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it. Land rolling. Soil 1st rate. Good grass.
2.00	From the 1/16 Sec. corner 20 chs. S. of the ¼ Sec. corner between Secs 13 & 24. I run South on true line in Sec. 24. Var. 19° E. Gulch course N. W.