

Allotment

Section 24

Subdivision of Township 3 North Range 35 East

Chains 10.00	<p>Set stone 10x8x7 ins. 6 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face, dug pits 18x18x12 ins. N. & S. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.</p> <p>Land rolling Soil 1st rate. Good grass.</p>
	<p>From the 1/32 Sec. corner 10 chs. N. of the ¼ Sec. 19 & 24 which is a basalt stone 12x10x4 ins. 8 ins. in the ground for 1/32 Sec. corner marked 1/32 on W. face. With pits 18x18x12 ins. N. & S. of stone 5½ ft. dist. mound of earth 1½ ft. high 3½ ft. base over it. I run West on random line in Section 24.</p> <p style="text-align: right;">Var. 19° E.</p>
41.60	<p>Setting temporary corner at 20, 80 chs. and at Intersect the N. & S. line at 1/32 Sec. corner 30 chs. S. of ¼ Sec. corner between Secs 13 & 24. Thence I run East on true line in Sec. 24.</p> <p style="text-align: right;">Var. 19° E.</p>
11.60	Ascend to Summit & descend.
19.60	Gulch Course N. W.
20.80	<p>Set stone 9x8x8 ins. 6 ins. in the ground for 1/32 Sec. corner marked 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base over it.</p>
41.60	<p>To the 1/32 Sec. corner.</p> <p>Land rolling. Soil 1st rate. Good grass.</p>
	<p>From the corner to Secs. 19-24-25 & 30 which is a basalt stone 12x10x8 ins. 8 ins. in the ground marked 4 notches on N. & 2 notches on S edges, and dug pits 18x18x12 ins. in each Sec. 5½ ft. dist. & mound of earth 2 ft. high 4½</p>