

83  
Allotment  
Section 24

Subdivision of Township 3 North Range 35 East

Chains	Pits impracticable.
30.00	Set post 3 ft. long 3 ins. sq. with marked stone 12 ins. in the ground for 1/16 Sec. corner marked 1/16 S. on W. face, dug pits 18x18x12 ins. N & S. of post 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.
35.00	Summit
47.50	Gulch course W.
50.00	To the 1/16 Sec. corner 20 chs. W. of the corner to Secs. 19-24-25 & 30. Land rolling with one rocky canyon. Timber along gulch Good grass, sunflower. Soil 1st rate & rocky in places.

Section 25

From the 1/16 & 1/32 Sec. corner 20 chs. W. of corner to Secs. 19-24-25 & 30. I run South on true line in Section 25.  
Var. 20° East.

Over rolling hill.

10.00	Set stone 11x10x6 ins. 6 ins. in the ground for 1/32 Sec. corner marked 1/32 on W. face, dug pits 18x18x12 ins. N & S. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.
-------	---

Land rolling

Soil 1st rate.

Good grass

From the 1/32 Sec. cor. 20 chs. W. & 10 chs. S. of corner to Secs. 19-24-25 & 30. I run

West on true line in Sec. 25

Var. 21° East.

15.00	Down ravine S.
-------	----------------

20.90	Set stone 12x9x7 ins. 10 ins. in the ground for 1/32 Sec. corner marked 1/32 on N. face, Dug pits 18x18x12 ins.
-------	---