

Allotment

Section 26

Subdivision of Township 3 North Range 35 East.

Chains	
39.95	<p>Setting temporary Corner at 20.00 chains and at Intersect the West bdy. of Sec. 26. 35 lks. S. of $\frac{1}{4}$ Sec. corner between Secs. 26 & 27. which is a charred stake 12 ins. in the ground with pits 18x18x12 ins. N. & S. of stake $5\frac{1}{2}$ ft. dist. & mound of earth $1\frac{1}{2}$ ft. $3\frac{1}{2}$ ft. base over it. In N. pit a stake 2 ins. square firmly set in the ground marked $\frac{1}{4}$ S. on W. face. I run East on true line in Sec. 26.</p>
19.97	<p style="text-align: center;">Var. 20° East</p> <p>Set a basalt stone 14x8x6 ins. 10 ins. in the ground for $1/16$ & $1/32$ Sec. corner, marked $1/16$ on N. & $1/32$ on S. face and raised a mound of stone over it. Pits impracticable.</p>
29.86	<p>Set basalt stone 10x8x5 ins. 6 ins. in the ground for $1/32$ Sec. corner, marked $1/32$ on N. face; dug pits 18x18x12 ins. E. & W. of stone $5\frac{1}{2}$ ft. dist. and raised mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it.</p>
39.95	<p>To the $\frac{1}{4}$ Sec. corner at center of Sec. 26. Land rolling, Soil 1st rate. Grass & sunflower.</p>
20.00	<hr/> <p>From the $1/32$ Sec. corner 29.86 chains, E. of $\frac{1}{4}$ Sec. cor. between Secs. 26 & 27. I run South on true line in Sec. 26. Var. 19° E. Down a broad summit.</p> <p>Set a basalt stone 12x8x8 ins. 8 ins. in the ground near Creek of Canyon E. for $1/32$ Sec. corner marked $1/32$ on W. face. Dug pits 18x18x12 ins. N. & S. of stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base over it. Land rolling. Soil 1st rate. Grass & sunflower.</p>