

Allotment

Section 26

Subdivision of Township 3 North Range 35 East.

Chains.	<p>27 34 & 35. I run East on true line in Sec. 26 Var. 21° East.</p>
20.00	<p>Set stone 10x9x7 ins. 7 ins. in the ground for 1/32 Sec. marked 1/32 N. face dug pits 18x18x12 ins. E. & W. of stone 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ ft. base over it. Land mostly level. Soil rich. Grass & Sunflower.</p>
10.00	<p>From the 1/32 Sec. corner 10 chs. N. & 20 chs. E. of corner to Secs. 26, 27, 34 & 35. I run North on random line in Sec. 26. Var. 21° E. Intersect the E. & W. line at 1/32 Sec. corner. Thence I run South on true line in Sec. 26 Var. 21° E.</p>
4.00	Trqll course S. E.
10.00	<p>To the 1/32 Sec. corner. Land mostly level. Grass & Sunflower Rich soil. June 10, 1889.</p>
Section 31	
20.00	<p>From the ¼ Sec. corner bet. Secs. 31 & 32 which is a stone 32x10x6 ins. 8 ins. in the ground marked ¼ on W. face, dug pits 18x18x12 ins. N. & S. from stone 5½ ft. dist. & raised mound of earth 1½ ft. high 3½ ft. base over it. I run S. 1° 30' E. on true line between Secs. 31 and 32. Var. 19° East. Set stone 16x10x9 ins. 10 ins. in the ground for 1/16 Sec. corner, marked 1/16 on W. face and raised a mound of stone</p>