

## Allotment

## Section 34.

## Subdivision of Township 3 North Range 35 East

Chains	
20.00	<p>From the 1/16 Sec. corner 20 chs. E. of the corner to Secs. 27, 28, 33 &amp; 34. which is a stone 12x6x6 ins. marked 1/16 on N. face pits 18x18x12 ins. E. &amp; W. of stone 5½ ft. dist. &amp; mound of earth 1½ ft. high 3½ ft. base over it. I run</p> <p>South on true line in Secs. 34.</p> <p style="text-align: right;">Var. 20° E.</p> <p>Across plowed land descending W.</p> <p>Set stone 16x10x8 ins. 10 ins. in the ground for 1/16 Sec. cor. marked 1/16 on W. face and raised a mound of stone over it.</p> <p>Pits impracticable.</p> <p>Land rolling.</p> <p>Soil 1st rate.</p> <p>Cultivated.</p>
19.00	<p>From the 1/16 Sec. corner 20 chs. E. &amp; 20 chs. S. of cor. to Secs. 27, 28, 33 &amp; 34. I run</p> <p>West on random on line in Section 34.</p> <p style="text-align: right;">Var. 20° E.</p> <p>Intersected the N. &amp; S. line 10 chs. S. of 1/16 Sec. cor. bet. Secs. 33 &amp; 34. which is a stone 14x8x6 ins. 9 ins. in the ground marked 1/16 on W. face with pits 18x18x12 ins. N. &amp; S. of stone 5½ ft. dist. &amp; a mound of earth 1½ ft. high 3½ ft. base over it.</p> <p>Thence I run</p> <p style="text-align: center;">S 89° 42' E on true line in Sec. 34.</p> <p style="text-align: right;">Var. 20° E.</p>
19.00	<p>To 1/16 Sec. corner in Sec. 34.</p> <p>Land sloping to South.</p> <p>Soil 1st rate.</p> <p>Mostly plowed.</p>