

Allotment 35114

Section 35

Subdivision of Township 3 North Range 35 East.

Chains

From the $\frac{1}{4}$ Sec. corner bet Secs. 35 & 36, which is a post
3 ins. sq. firmly set in the ground marked $\frac{1}{4}$ S. on W.
face, from which

A pine 6 ins. diam bears N. 88° E. 36 lks. dist.
marked $\frac{1}{2}$ S B T.

A pine 6 ins. diam. bears S. 35° W. 31 lks. dist.
marked $\frac{1}{4}$ S B T.

I run

S 2° 55' E. on true line bet Secs 35 & 36.

Var. 20° E.

Ascend brushy hill.

20.00 Summit & set stone 12x8x8 ins. 8 ins. in the ground for
1/16 Sec. corner marked 1/16 on W. face, raised a mound
of stone over it.

Pits impracticable.

Along S. slope rocky.

30.00 Set basalt stone 10x8x7 ins. 6 ins. in the ground for 1/32
Sec. corner marked 1/32 on W. face & raised a mound of
stone over it.

Pits impracticable.

39.83 The corner to Secs. 35 & 36 on South bdy. of Township
which is a basalt stone 18x12x4 ins. 12 ins. in the
ground marked with 1 notch on E. & 5 notches on W. edges
& mound of stone over it.

Land mountainous 1st 20 chs.

Soil 1st rate & pine & other brush.

Bal. rocky & barren.

From the $\frac{1}{4}$ Sec. corner on S. bdy. of Sec. 35 which is a
basalt stone 12x10x5 ins. 8 ins. in the ground marked
 $\frac{1}{4}$ on N. face, and mound of stone over it.

I run

N. 89° 50' E. on random line on the S. bdy. of Sec. 35

Var. 21° E.