

35
Allotment
Section 35

Subdivisions of Township 3 North Range 35 East.

Chains	
	<p>Land mountainous. Soil 1st rate. Brush and grass.</p>
	<p>From 1/16 and 1/32 Sec. corner 20 chs. E. of corner to Secs. 34 & 35.</p> <p>I run N 2° 45' W. on true line in Sec. 35. Var. 21° E.</p> <p>Descend.</p>
9.35	<p>Set stone 18x18x6 ins. 12 ins. in the ground for 1/32 Sec. corner, marked 1/32 on W. face, dug pits 18x18x12 ins. N. & S. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.</p>
17.00	Descend Bluff
18.50	Foot of bluff. -100
19.35	<p>Set stone 10x8x7 ins. 7 ins. in the ground for 1/16 Sec. corner marked 1/16 on W. face; dug pits 18x18x12 ins. N. & E. of stone 5½ ft. dist. and raised a mound of earth 1½ ft. high 3½ ft. base over it.</p> <p>Land rough and steep on Bluff.</p> <p>Balance soil 1st rate.</p> <p>Grass and some brush</p>
	<p>From the 1/16 Sec. corner 20 chs. E. and 20 chs. N. of cor. to Secs. 34 & 35.</p> <p>I run East on random line in Sec. 35. Var. 21° East</p> <p>Setting temporary corner at 10, 20, and 40 chains and at</p>
59.55	<p>Intersect the N. & S. line 15 chs. S. of 1/16 Sec. cor. between Sec. 35 & 36.</p> <p>Thence I run S 89° 55' W on true line in Sec. 35. Var. 20° E.</p> <p>Descend.</p>