

90

Allotment

Section 35

Subdivision of Township 3 Range 35 East.

Chains 15.25	Gulch course N.	
19.85	Set basalt stone 11x8x7 ins. 7 ins. in the ground for 1/16 & 1/32 Sec. corner; marked 1/16 on N. and 1/32 on S. faces, dug pits 18x18x12 ins. E. & W. of stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it.	
39.70	Set stone 9x8x7 ins. 6 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face dug pits 18x18x12 ins. E. & W. of stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it.	
49.62	Set stone 12x10x8 ins. 8 ins. in the ground for 1/64 Sec. corner marked 1/64 on N. face, dug pits 18x18x12 ins. E. & W. of stone 5 1/2 ft. dist and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it.	
58.40	Foot of bluff	-100
59.55	To the 1/16 Sec. corner. Land rolling. Soil 1st rate. Scattering Pine Brush. Grass & Sunflower.	
From 1/16 Sec. corner 20 chs. North of 1/4 Sec. corner on the South Bdy. of Sec 35		
I run		
N. 2° 50' W. on true line in Sec. 35		
Var. 21° E.		
10.00	Set post 3 ft. long 3 ins. sq. 24 ins. in the ground for 1/64 Sec. corner marked 1/64 on W. face; from which A pine 6 ins. diam. bears North 41 lks. dist. marked 1/64 S B T. A pine 6 ins. diam. bears South 74 lks. dist. marked 1/64 S B T.	
17.00	Foot of steep hill	-75
18.25	Wagon Road course N. & S.	
18.60	Rail Road N. 80° W.	