

Allotment

Section 35

Subdivision of Township 3 North Range 35 East.

Chains	
	<p>I run</p> <p>East on random line in Sec. 35</p> <p style="text-align: right;">Var. 20° E.</p> <p>Setting temporary corner at 20 chains and at</p>
39.68	<p>Intersect the N. & S line 12 lks. S. of $\frac{1}{4}$ Sec. corner bet. Secs. 35 & 36.</p> <p>I run</p> <p style="text-align: center;">S 89° 50' W. on true line in Sec. 35</p> <p style="text-align: right;">Var. 20° E.</p>
17.00	Foot of hill and enter bottom.
19.84	<p>Set stone 10x8x6 ins. 6 ins. in the ground for 1/16 Sec. corner marked 1/16 on N. face, dug pits 18x18x12 ins. E. & W. stone 5$\frac{1}{2}$ ft. dist. and raised a mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base over it.</p>
35.00	Road Course S. W.
38.25	Railroad, S. W.
39.68	<p>To the $\frac{1}{4}$ Sec. corner in the center of Sec 35.</p> <p>Land rolling & steep.</p> <p>Grass, brush with some fine timber.</p> <p>Soil 1st rate, where it is not rocky.</p>
	<p>From the 1/32 Sec. corner 9.83 chs. N. of the S. E. corner of Sec. 35. I run</p> <p style="text-align: center;">S 89° 50' W. on true line in Sec. 35.</p> <p style="text-align: right;">Var. 19° E.</p>
3.00	<p>Summit course N. E.</p> <p>Descend to</p>
19.84	<p>Set post 3 ft. long 3 ins. sq. with charred stake 12 ins. in the ground for 1/32 Sec. corner; marked 1/32 on N. face, dug pits 18x18x12 ins. E. & W. of post 5$\frac{1}{2}$ ft. dist. and raised a mound of earth 1$\frac{1}{2}$ ft. high 3$\frac{1}{2}$ ft. base around post.</p> <p>Land rolling.</p> <p>Soil 1st rate.</p> <p>Grass.</p>