

30
Allotment

Section 35

Subdivision of Township 3 North Range 35 East.

Chains		
	<p>From the corner to Secs. 34 & 35 on the South bdy. of the Tp. I run North 2° 45' W. on true line between Secs 34 & 35. Var. 23° E.</p>	
6.50	Descend bluff & in dense brush	-75
9.35	<p>A willow tree 8 ins. in diam. which I mark 1/32 S. on W. face; for 1/32 Sec. corner, from which</p> <p>A Thorn 5 ins. diam. bears N. 45° W. 5 lks. dist. marked 1/32 S B T.</p> <p>A willow 5 ins. diam bears S. 40° E. 14 lks. dist. marked 1/32 S B T.</p> <p>From the corner the R. R. is situated about 4.00 chs. S.W. line.</p> <p>Brushy & rough, some grass.</p> <p>Soil 1st rate.</p>	
	<hr/> <p>From the 1/32 Sec. corner 9.35 chains N. of the corner to Secs. 34 & 35 on S. bdy. of T. I run N 89° 50' E. on random line in Sec. 35. Var. 20° E.</p>	
20.15	<p>Intersect the line at point 10 lks. N. of 1/32 Sec. Corner in Sec. 35.</p> <p>Thence I run N. 89° 53' W. on true line in Sec. 35. Var. 17° 30' E.</p>	
	Ravine Course N.	-10
16.00	Descend bluff	-100
20.15	<p>To the 1/32 Sec. corner, between Secs. 34 & 35.</p> <p>Land rolling, Grass.</p> <p>Brush on bottom.</p>	
	<hr/> <p style="text-align: center;">Section 36</p> <p>From $\frac{1}{4}$ Sec. corner bet. Secs. 35 & 36. I run N. 89° 50' E. on true line in Sec 36 Var. 20° E.</p>	