

Allotment

Section 36
Subdivision of Township 3 North Range 35 East.

Chains 15.00	From 1/32 Sec. corner 10 chs. N. of 1/4 Sec. corner in the center of Sec. 36. I run West on true line in Sec. 36. Through open ground. Bluff.	
20.00	Set stone 12x8x7 ins. 8 ins. in the ground for 1/32 Sec. corner marked 1/32 on S. face, and dug pits 18x18x12 ins. E. & W. of stone 5 1/2 ft. dist. and raised a mound of earth 1 1/2 ft. high 3 1/2 ft. base over it. Land mostly level, part bluff. Soil 1st rate except on bluff. Good grass.	-100.
<p>General Description.</p> <p>These lands, are situated mostly on table land, North of the Umatilla River, balance along the River.</p> <p>Soil is 1st rate or rocky.</p> <p>Good grass on upland & brushy along river.</p>		
<p>Survey of the Sub-Subdivisional Lines of Township 3 North Range 35 East. Willamette Meridan, Oregon, as surveyed by Jas. P. Currin and Jas. E. Noland U.S. Deputy Surveyor, under their Contract No. dated May 4, 1887. Survey commenced Sept. 26, 1887. Survey completed Oct. 4, 1887.</p>		
79.48 19.87	Commencing at 1/16 Sec. cor. 20 chains S. of 1/4 Secs. 22 and 23. I run East on random through S. 1/2 of Sec. 23. Var. 21° East. Set temporary cors. at 20, 40 and 60 chains and at Intersect E. bdy 50 lks. S. of 1/16 Sec. cor. Thence S. 89° 39' West on true line. Ascend steep mountain side. Set basalt stone 10x8x8 ins. 6 ins. in the ground for	