

## Sub Divisions of Township 3 North 35 East.

Chains	
	1/16 Sec. cor, dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. and raised mound of earth 1½ ft. high 3½ base over it. and marked stone 1/16 on N. face.
25.00	Top of ridge on summit bears S.
39.74	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it, and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
59.61	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist raised mound of earth 1½ ft. high 3½ ft. base over it, and in E. pit drove stake 2 ft. long 2 ins. sq. 12 ins. in the ground marked 1/16 S. on N. face.
79.48	To point of beginning. Land rolling. Soil 2nd rate.
Commencing at ¼ Sec. cor. bet. Secs. 22 & 23. Thence East on random through Center of Sec. 23. Var. 21° East.	
79.30	Set temp. cor. at 20, 40 and 60 chains and at Intersect E. bdy. 40 lks. S. of ¼ Sec. cor. Thence S. 89° 43' W. on true line. Ascend.
10.00	Summit of hill
19.82	Deposited charred stake 12 ins. in the ground for 1/16 Sec. cor. dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it and in E. pit drove stake 2 ft. long 2 ins. square 12 ins. in the ground marked 1/16 S. on N. face.
39.65	Deposited charred stake 12 ins. in the ground for ¼ Sec. cor. dug pits 18x18x12 ins. E. & W. of stake 5½ ft. dist. raised mound of earth 1½ ft. high 3½ ft. base over it. And in E. pit drove stake 2 ft. long 2 ins. Square 12

\$150